# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
## Office of the Executive Engineer, Dasarahalli Division
### Schedule-B

NAME OF THE WORK: Construction of RCC drain & Improvements to Cross roads, 1st, 2nd, 3rd, 4th, 5th & culvert at Grape Garden T.Dasarahalli Ward No.15.

| Sl. No | Description of work | Unit | Qty | Approved Rates | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | Earthwork excavation by manual means in Hard Soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 9 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of Engineer-in-charge of the work | cum | 573.12 | 208.82 | Rupees Two Hundred Eight and Eighty Two Paise Only |
| | : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and | | | | Rupees Five |

| | | | | | |
|---|---|---|---|---|---|
| 6 | Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials | sqm | 361.80 | 1698.00 | Rupees One Thousand Six Hundred Ninety Eight Only |
| 7 | Providing and fixing Pre cast solid cement concrete kerb stones made out of No272.21 C.C 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc | No.s | 846.00 | 331.78 | Rupees Three Hundred Thirty One and Seventy Eight Paise Only |
| 8 | Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications | sqm | 152.28 | 63.60 | Rupees Sixty Three and Sixty Paise Only |